

Test Report PPR-3203

Test objects: Cold shrink Medium Voltage Termination 42kV CSTI/O-6142-ML-6-17
charcoal grey

Test performed: CENELEC HD 629.1 S3:2015 table 6/7, page 17/18

Pages: 29 incl. Installation instruction EPP-2828-8/16

Tested by: **Maximilian Biegel** Signature: *M. Biegel* Date: 8/11-2016
Lab technician

Prepared by: **Ernst Liegl** Signature: *E. Liegl* Date: 8/11-2016
Application Engineer

Released by: **Per Christian Olving** Signature: *P. Olving* Date: 8/11-2016
Product Manager

Tyco Electronics Raychem GmbH
Energy Division
Finsinger Feld 1
D-85521 Ottobrunn
Munich, Germany
Tel.: +49-89-6089-0
Fax: +49-89-6096-345

© Raychem Reports may only be used in their original form

Subject of Test:	In- and Outdoor Termination type CSTI/O charcoal grey for 42kV for Single Core Polymeric Cables
Date of Tests:	August 2016 – October 2016
Requirements:	CENELEC HD 629.1 S3:2015 table 6/7, page 17/18
Manufacturer:	Tyco Electronics Raychem GmbH, Ottobrunn - Germany
Location of Tests:	Tyco Electronics Raychem Energy Laboratories, Ottobrunn - Germany
Test Purpose:	Qualification testing of CSTO charcoal grey on 36kV single core standard cable, according to CENELEC HD 629.1 S3:2015 table 6/7, page 17/18
Reference:	Laboratory Book
Test Results:	All samples passed the test requirements in accordance with the CENELEC HD 629.1 S3:2015 table 6/7, page 17/18 for the voltage class 20,8/36(42) kV.

Contents:

1	Qualification Test for CSTI/O charcoal grey Termination	4
1.1	Test Programme.....	4
1.2	Cable identification.....	6
1.3	Test Setup.....	8
1.3.1	AC voltage withstand test.....	8
1.3.2	Partial discharge test.....	9
1.3.3	Impulse voltage test.....	10
1.4	Test Sequence	11
1.4.1	AC voltage test according to section 4 EN 61442.....	11
1.4.2	Partial Discharge test at ambient temperature according to section 7 EN 61442.....	11
1.4.3	Impulse voltage withstand test at elevated temperature acc. to section 6 EN61442	12
1.4.4	Continuous AC voltage test with cyclic current load acc. to section 9 EN 61442	16
1.4.5	Immersion test acc. to section 9 EN 61442	17
1.4.6	Partial Discharge test according to section 7 EN 61442.....	18
1.4.7	Impulse voltage withstand test at ambient temperature acc. to section 6 EN61442.....	18
1.4.8	AC voltage test according to section 4 EN 61442.....	22
1.4.9	Partial Discharge test at ambient temperature according to section 7 EN 61442.....	23
1.5	Summary Test Results.....	24
1.6	Appendix	24

1 Qualification Test for CSTI/O charcoal grey Termination

1.1 Test Programme

The test sequence of the terminations for 20,8/36 (42) kV was done in accordance with HD 629.1 S3:2015 table 6/7, page 17/18.

Table 1: Terminations for extruded insulation cables

	Test	Test clause of EN 61442	Test sequence			Test requirements
			A1	A2	A3	
1	AC voltage dry withstand	4	X			5 min. at 93,5 kV
2	Partial discharge at ambient temperature	7	X			max. 10 pC at 42 kV
3	Impulse voltage at elevated temperature	6	X			10 +/- 200 kV
4	Electrical heat cycling in air	9	X			126 Cycles 5/3 52 kV 95-100°C
5	Immersion Only outdoor termination	9.4	X			10 Cycles
6	Partial discharge at ambient - ambient temperature - elevated temperature	7	X			max. 10 pC at 42 kV max. 10 pC at 42 kV
7	Impulse voltage at ambient temperature	6	X			10 +/- 200 kV
8	AC voltage dry withstand	4	X			5 min. at 93,5 kV
9	Partial discharge at ambient temperature	7	X			max. 10 pC at 42 kV
10	Examination					

1.2 Cable identification

Rated voltage U_0/U (U_m):	18/30 (36) kV		
Construction:	<input checked="" type="checkbox"/> 1-core	<input type="checkbox"/> 3-core	<input type="checkbox"/> Individually screened
			<input checked="" type="checkbox"/> Overall screen
Conductor:	<input type="checkbox"/> Al	<input checked="" type="checkbox"/> Cu	
	<input checked="" type="checkbox"/> Stranded	<input type="checkbox"/> Solid	
	<input checked="" type="checkbox"/> Circular	<input type="checkbox"/> Shaped	
	<input type="checkbox"/> 120mm ²	<input type="checkbox"/> 150mm ²	<input checked="" type="checkbox"/> 185mm ²
	<input type="checkbox"/> Other cross section:	<input type="checkbox"/> 400mm ²	
Insulation:	<input checked="" type="checkbox"/> XLPE		
	<input type="checkbox"/> EPR	<input type="checkbox"/> HEPR	
Insulation screen:	<input checked="" type="checkbox"/> Bonded	<input type="checkbox"/> Strippable	
Metallic screen:	<input type="checkbox"/> Wire	<input type="checkbox"/> Tape	<input checked="" type="checkbox"/> Extruded
Armour:	<input type="checkbox"/> Wire	<input type="checkbox"/> Tape	
Over sheath:	<input type="checkbox"/> PVC	<input checked="" type="checkbox"/> PE (state type)	
Water blocking, if any:	<input type="checkbox"/> In conductor	<input checked="" type="checkbox"/> Under over sheath	
Diameters:	Conductor:	mm 17,0	
	Insulation:	mm 33,1	
	Insulation screen:	mm 34,1	
	Over sheath:	Mm 42	
Cable marking:	TFKABLES NA2XS2Y 1x185 RM25 18/30 VDE0276		



Rated voltage U0/U (Um):	18/30 (36) kV		
Construction:	<input checked="" type="checkbox"/> 1-core	<input type="checkbox"/> 3-core	<input type="checkbox"/> Individually screened
			<input checked="" type="checkbox"/> Overall screen
Conductor:	<input checked="" type="checkbox"/> Al	<input type="checkbox"/> Cu	
	<input checked="" type="checkbox"/> Stranded	<input type="checkbox"/> Solid	
	<input checked="" type="checkbox"/> Circular	<input type="checkbox"/> Shaped	
	<input type="checkbox"/> 120mm ²	<input type="checkbox"/> 150mm ²	<input type="checkbox"/> 185mm ²
	<input type="checkbox"/> Other cross section:	<input checked="" type="checkbox"/> 400mm ²	
Insulation:	<input checked="" type="checkbox"/> XLPE		
	<input type="checkbox"/> EPR	<input type="checkbox"/> HEPR	
Insulation screen:	<input checked="" type="checkbox"/> Bonded	<input type="checkbox"/> Strippable	
Metallic screen:	<input type="checkbox"/> Wire	<input type="checkbox"/> Tape	<input checked="" type="checkbox"/> Extruded
Armour:	<input type="checkbox"/> Wire	<input type="checkbox"/> Tape	
Over sheath:	<input type="checkbox"/> PVC	<input checked="" type="checkbox"/> PE (state type)	
Water blocking, if any:	<input type="checkbox"/> In conductor	<input checked="" type="checkbox"/> Under over sheath	
Diameters:	Conductor:	mm 23,5	
	Insulation:	mm 41	
	Insulation screen:	mm 42,9	
	Over sheath:	mm 51	
Cable marking:	CABLEL 2011 NA2XS2Y 1x400 RM35 18/30 VDE0276		

1.3 Test Setup

1.3.1 AC voltage withstand test

The AC voltage was generated by a 350kV transformer (see figure 3). The voltage measurement was carried out with a capacitive divider.

Test circuit: technical data

Tr	Test transformer:	350 kV, 175 kVA, 50 Hz
C-Div	Capacitive divider	75 pF
TO	Test objects	




Figure 3: AC test circuit diagram

Measuring equipment:

Object	Type	Calibration number	Calibration date
Capacitive divider	MCF75/350P/MC	1303/DKD/-K-24501/04-11	2015-03-10
Measurement cable		1303/DKD/-K-24501/04-11	2015-03-10
AC peak voltmeter	LDIC-voltage unit	1303/DKD/-K-24501/04-11	2015-03-10

The correction factor for the voltage metering, defined during the calibration, was specified to a value of 0,984. The relative measurement uncertainty of the test circuit was 1,2 %.

1.3.2 Partial discharge test

The partial discharge test was performed according to figure 4. The voltage measurement was carried out with a capacitive divider. For the extraction of the partial discharge signals a separate capacitive divider was used. The background noise level at test voltage was < 1 pC. Prior to the test, the complete test arrangement including the test object has been calibrated.

Test circuit: technical data

Tr	Test transformer:	350 kV, 175 kVA, 50 Hz
C-Div ₁	Capacitive divider	75 pF (voltage measurement)
C-Div ₂	Capacitive divider	1000 pF (partial discharge measurement)
TO	Test object	




Figure 4: PD test circuit diagram

Measurement equipment:

Object	Type	Calibration number	Calibration date
Calibrator tester	LDC-5/S1	00325201	2015-03-10

1.3.3 Impulse voltage test

For the test an impulse generator with a maximum charging voltage of 800kV and a maximum impulse energy of $E_{max} = 24$ kJ was used (see figure 5). The voltage measurement was carried out with a resistive-capacitive divider and an impulse measurement system. The relative measurement uncertainty was 1,2 %

Test circuit: technical data

Number impulse generator stages:	4
RC-Div Damped-Capacitive Divider	Ratio: 800 : 1,4
TO Test objects	




Figure 5: Impulse test circuit diagram

Measurement equipment:

Object	Type	Calibration number	Calibration date
Damped capacitive divider	CS 1000	1302/DKD/-K-24501/04-11	2015-03-10
Measurement cable		1302/DKD/-K-24501/04-11	2015-03-10
Digital recorder	DIAS 730	1302/DKD/-K-24501/04-11	2015-03-10

1.4 Test Sequence

1.4.1 AC voltage test according to section 4 EN 61442

AC voltage of 93,5 kV_{rms}, 50 Hz was applied between the conductor and the grounded screen for 5 minutes. The voltage was continuously increased within 10 seconds to the specified value and then held constant during the required test period.

relative humidity of air	atmospheric pressure	temperature
71 %	955 hPa	25° C

Result: All samples passed

1.4.2 Partial Discharge test at ambient temperature according to section 7 EN 61442

The lugs were made corona-free by using ring electrodes and an AC test voltage of 2.0 U₀ was applied for 1 minute. Then the voltage was decreased to the AC test voltage U_{PD} = 42 kV and within 1 minute the maximum value of the partial discharge magnitude was measured.

relative humidity of air	atmospheric pressure	temperature
71 %	955 hPa	25° C

	Loop 1	Loop 2	Loop 3	Loop 4
	185mm ²	185mm ²	185mm ²	185mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

	Loop 1	Loop 2	Loop 3	Loop 4
	400mm ²	400mm ²	400mm ²	400mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 5pC	< 1pC

Admissible Partial Discharge Magnitude: 10 pC


Result: All samples passed

1.4.3 Impulse voltage withstand test at elevated temperature acc. to section 6 EN61442

An impulse voltage with rise time approx. 1.2 μ s and half-value decay time with approx. 50 μ s was applied. The test loop was exposed to 10 impulses each of an impulse voltage of 200 kV of positive and negative polarity between the conductor and the grounded screen.

relative humidity of air	atmospheric pressure	temperature
70 %	955 hPa	26 °C

Sample 185mm² CSTI/O



Imp. elevated Temp 200kV 10+/- Loop 1 - 4 □□CSTI und CSTO

Environmental Conditions: 955 hPa 70 % 26 °C Tested by: NOS



1/1

Fig. 1: Impulse oscillograms for 185mm² XLPE cable, loop 1- 4

The impulse oscillograms in figure 1 don't show any discrepancies from the calibration oscillogram.


Result: All samples passed

Sample 400mm² CSTI/O


elevated Imp. 200 kV 10+/-□□CSTI und CSTO Loop 1-4 400mm
Environmental Conditions: 953 hPa 62 % 25 °C

Tested by: MXB


No. 1 LI full Upk: 198.494 kV T1: 1.323 us T2: 50.461 us




No. 2 LI full Upk: 201.883 kV T1: 1.329 us T2: 50.437 us




No. 3 LI full Upk: 201.831 kV T1: 1.330 us T2: 50.392 us




No. 4 LI full Upk: 201.774 kV T1: 1.321 us T2: 50.428 us




No. 5 LI full Upk: 201.722 kV T1: 1.328 us T2: 50.478 us




No. 6 LI full Upk: 201.746 kV T1: 1.331 us T2: 50.434 us




No. 7 LI full Upk: 201.782 kV T1: 1.325 us T2: 50.494 us




No. 8 LI full Upk: 201.585 kV T1: 1.328 us T2: 50.475 us



No. 9 LI full Upk: 201.730 kV T1: 1.336 us T2: 50.470 us




No. 10 LI full Upk: 201.684 kV T1: 1.335 us T2: 50.449 us




elevated Imp. 200 kV 10+/- CSTI und CSTO Loop 1-4 400mm
Environmental Conditions: 953 hPa 62% 25 °C

Tested by: MXB


LI full Upk: -200.771 kV T1: 1.014 us T2: 49.904 us




LI full Upk: -201.339 kV T1: 1.011 us T2: 49.803 us




LI full Upk: -201.525 kV T1: 975.645 ns T2: 49.754 us




LI full Upk: -201.203 kV T1: 1.016 us T2: 49.847 us




LI full Upk: -201.413 kV T1: 1.012 us T2: 49.856 us




LI full Upk: -201.249 kV T1: 1.009 us T2: 49.896 us




LI full Upk: -201.394 kV T1: 1.008 us T2: 49.816 us



LI full Upk: -201.154 kV T1: 1.013 us T2: 49.862 us



LI full Upk: -201.364 kV T1: 1.007 us T2: 49.819 us



LI full Upk: -201.285 kV T1: 1.010 us T2: 49.938 us




Fig. 2: Impulse oscillograms for 400mm² XLPE cable, loop 1- 4

The impulse oscillograms in figure 2 don't show a discrepancy from the calibration oscillogram.



Result: All samples passed

1.4.4 Continuous AC voltage test with cyclic current load acc. to section 9 EN 61442

The test loop, suspended free in air, was subjected to 126 load cycles with a continuously applied AC test voltage of 52 kV. Each load cycle consist of a 3 hours load period, 2 hours hold period and 3 hours cooling period. The current was adjusted to a level which heated up the cable core to a temperature of 95° C. The ambient temperature during the load cycles was approx. 24° C.




Fig. 3: Temperature during one load cycle

Result: All samples passed

1.4.5 Immersion test acc. to section 9 EN 61442

The terminations of a test loop, were immersed in water at ambient temperature with a height of water 0,03m above every part of the termination. The test loop was installed upside down in a water tank at ambient temperature, in such a way that the terminations were fully immersed in water, including the end of the sealing element. The test loop was subjected to 10 load cycles each cycle consist of a 3 hours load period, 2 hours hold period and 3 hours cooling period. The current was adjusted to a level which heated up the cable core to a temperature of 95° C. The ambient temperature during the load cycles was approx. 24° C.




Fig. 4: Temperature during one load cycle

Result: All samples passed

1.4.6 Partial Discharge test according to section 7 EN 61442

After the 126th load cycle the Partial Discharge test as in 1.4.2 was repeated.

a) Partial Discharge Test at ambient temperature

relative humidity of air	atmospheric pressure	temperature
38 %	953 hPa	25° C

	Loop 1	Loop 2	Loop 3	Loop 4
	185mm ²	185mm ²	185mm ²	185mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

	Loop 1	Loop 2	Loop 3	Loop 4
	400mm ²	400mm ²	400mm ²	400mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

Admissible Partial Discharge Magnitude: 10 pC

Result: All samples passed

b) Partial Discharge Test at elevated temperature

The PD-Measurement was done as in 1.4.2, but the conductors were heated up to a temperature of 95 - 100° C.

relative humidity of air	atmospheric pressure	temperature
38 %	953 hPa	25° C

	Loop 1	Loop 2	Loop 3	Loop 4
	185mm ²	185mm ²	185mm ²	185mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

	Loop 1	Loop 2	Loop 3	Loop 4
	400mm ²	400mm ²	400mm ²	400mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

Admissible Partial Discharge Magnitude: 10 pC

Result: All samples passed


1.4.7 Impulse voltage withstand test at ambient temperature acc. to section 6 EN61442



An impulse voltage with rise time approx. 1.2 μ s and half-value decay time with approx. 50 μ s was applied. The test loop was exposed to 10 impulses each of an impulse voltage of 200 kV of positive and negative polarity between the conductor and the grounded screen.


relative humidity of air	atmospheric pressure	temperature
35 %	952 hPa	25° C

Sample 185mm² CSTI/O



Imp. Test amb.Temp. 10 +/- 200kV Loop1-4 400sqmm
Environmental Conditions: 955 hPa 46 % 24 °C

Tested by: NOS



1/1

Fig. 5: Impulse oscillograms for 185mm² XLPE cable, loop 1- 4

The impulse oscillograms in figure 5 don't show any discrepancies from the calibration oscillogram.


Result: All samples passed
Sample 400mm² CSTI/O

Imp. Test amb.Temp. 10 +/- 200kV □□ Loop1-4 400sqmm
Environmental Conditions: 955 hPa 46 %


24 °C

Tested by: NOS


No. 1 LI full Upk: 200.676 kV T1: 1.125 us T2: 47.558 us




No. 2 LI full Upk: 200.641 kV T1: 1.125 us T2: 47.506 us




No. 3 LI full Upk: 200.497 kV T1: 1.122 us T2: 47.451 us




No. 5 LI full Upk: 200.137 kV T1: 1.113 us T2: 47.603 us




No. 4 LI full Upk: 200.190 kV T1: 1.125 us T2: 47.570 us




No. 6 LI full Upk: 200.050 kV T1: 1.118 us T2: 47.649 us




No. 7 LI full Upk: 200.421 kV T1: 1.120 us T2: 47.580 us




No. 8 LI full Upk: 200.480 kV T1: 1.130 us T2: 47.552 us



No. 9 LI full Upk: 200.676 kV T1: 1.116 us T2: 47.560 us



No. 10 LI full Upk: 200.522 kV T1: 1.111 us T2: 47.623 us



Imp. Test amb. Temp. 10 +/- 200kV Loop1-4 400sqmm
Environmental Conditions: 955 hPa 46 % 24 °C Tested by: NOS




Fig. 6: Impulse oscillograms for 185mm² XLPE cable, loop 1- 4

The impulse oscillograms in figure 6 don't show any discrepancies from the calibration oscillogram.

Result: All samples passed

1.4.8 AC voltage test according to section 4 EN 61442

AC voltage of 93,5 kV_{rms}, 50 Hz was applied between the conductor and the grounded screen for 5 minutes. The voltage was continuously increased within 10 seconds to the specified value and then held constant during the required test period.

relative humidity of air	atmospheric pressure	temperature
35 %	952 hPa	25° C

Result: All samples passed

1.4.9 Partial Discharge test at ambient temperature according to section 7 EN 61442

The lugs were made corona-free by using ring electrodes and an AC test voltage of 2.0 U₀ was applied for 1 minute. Then the voltage was decreased to the AC test voltage U_{PD} = 42 kV and within 1 minute the maximum value of the partial discharge magnitude was measured.

relative humidity of air	atmospheric pressure	temperature
35 %	952 hPa	25° C

	Loop 1	Loop 2	Loop 3	Loop 4
	185mm ²	185mm ²	185mm ²	185mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

	Loop 1	Loop 2	Loop 3	Loop 4
	400mm ²	400mm ²	400mm ²	400mm ²
	CSTI	CSTI	CSTO	CSTO
PD value @ 42kV	< 1pC	< 1pC	< 1pC	< 1pC

Admissible Partial Discharge Magnitude: 10 pC

Result: All samples passed




1.5 Summary Test Results

All samples passed the test requirements in accordance with the CENELEC HD 629.1 S3:2015 table 6/7, page 17/18 for the voltage class 20,8/36 (42) kV.

1.6 Appendix



Raychem
from TE Connectivity



Installation Instruction
EPP-2828-8/16

Raychem
Termination for Screened
Single Core Polymeric Cable
without Armour

Type: CSTI/CSTO
Indoor/Outdoor

36 kV / 42 kV

To view the TE Energy website:



Tyco Electronics Raychem GmbH
a TE Connectivity Ltd. Company
TE Energy
Finsinger Feld 1
85521 Ottobrunn/Munich, Germany
Tel: +49-89-6089-0
Fax: +49-89-6096-345
energy.te.com

Before Starting

Check to ensure that the kit you are going to use is suitable for the size of cables being jointed.

Refer to the kit label and the title of the installation instruction.

Components or working steps may have been modified since you last installed this product.

Carefully read and follow the steps in the installation instruction.

General Instructions

Clean and degrease all parts that will come into contact with adhesive.

If a solvent is used follow the manufacturer's handling instructions.

Check cable ends for ingress of moisture before starting with cable preparation.

For easy strip screen layers always use a round file to cut radially through the core screen.

The Information contained in these installation instructions is for use only by installers trained to make electrical power installations and is intended to describe the correct method of installation for this product. However, TE Connectivity has no control over the field conditions which influence product installation.

It is the user's responsibility to determine the suitability of the installation method in the user's field conditions. TE Connectivity's only obligations are those in TE Connectivity's standard Conditions of Sale for this product and in no case will TE Connectivity be liable for any other incidental, indirect or consequential damages arising from the use or misuse of the products.

Raychem, TE, TE Connectivity and TE connectivity (logo) are trademarks.

© 2016 TE Connectivity. All Rights Reserved.

Cable Preparation

Before Starting

Check to ensure that the kit you are going to use fits the cable.
 Refer to the kit label and the title of the installation instruction.
 Components or work steps may have been improved since you last installed this product.
 Carefully read and follow the steps in the installation instruction.


Table for cutback dimensions

Mechanical lug BLMT	Cable	Termination
	Cross Section	Indoor/Outdoor 36 kV/42 kV
	mm ²	mm
BLMT 25/95	95	435
BLMT 35/150	50 Cu	460
BLMT 35/150	150 Al	450
BLMT 95/240	185	475
BLMT 95/240	240	440
BLMT 120/300	120 – 300	
BLMT 185/400	185	475
	400	445
BLMT 500/630	500 Al	485
BLMT 500/630	630 Al	485
BLMT 500/630	630 Cu	485
BLMT 800/1000	1000 Al	460

For cable cross section 50 - 630 mm²

Cut the cable to the required length.
 Remove the oversheath according to L. Clean and degrease the end of the oversheath for approximately 100 mm.


Mark a line 70 mm below the oversheath cut.




For cable cross section 800 - 1000 mm²


Cut the cable to the required length.
 Remove the oversheath according to L. Clean and degrease the end of the oversheath for approximately 100 mm.

Mark a line 60 mm below the oversheath cut.




Wrap two layers of sealant tape (grey) with a small overlap and slight tension around the end of the oversheath as shown. Bend the shielding wires back onto the oversheath. Avoid crossing the individual wires. Fix the shielding wires with a tape to the oversheath.






3
Thoroughly remove the core screen to within 40 mm of the overshooth cut. The surface of the insulation should be free from all traces of conductive material. Smooth out any irregularities.

Note: Do not nick the insulation.



4
Cut back the insulation according to **Mechanical lugs:**
K = depth of cable lug barrel hole
Install the cable lug and remove all sharp edges. Clean and degrease the core insulation and the lug.



5
Apply a thin layer of silicone grease onto the insulation and the core screen cut.

Position the termination body. Pull the spiral gently until the termination body butts to the reference line.

If the termination is not correctly positioned, it is possible to gently slide it into place.



Remove the spiral holdout completely from the termination by pulling it counterclockwise.

Do not twist the spiral holdout during removal. Avoid the spiral to hook up over the termination.

Degrease and clean the termination.

Fix the shield wires with a wire binder along the lower edge of the termination body. Install the cable lug on the shield wires.

Termination completed.



Please dispose of all waste according to local environmental regulations.







CSTI/CSTO – Product family

Indoor

Outdoor



Min. clearances	Max. system voltage in kV	
	36	42
a Air clearance	as for local specifications	
b ph/ph and ph/ground in mm	35	45
d Between skirts in mm	25	35